

**Tuttle Creek Lake  
Big Blue River, Kansas**

**DAM SAFETY ASSURANCE PROGRAM  
EVALUATION REPORT**

Table of Contents

<u>Chapter and Sub-Chapter</u>	<u>Page</u>
1. Project Authorization	
1-01. Construction Authorization	1-1
1-02. Authorized Purposes	1-1
2. Project Description	
2-01. General	2-1
2-02. Embankment Dam	2-2
2-03. Site Seismicity	2-4
3. Current Conditions	
3-01. Current Condition of the Project Features	3-1
a. Embankment	
b. Outlet Works	
c. Spillway	
3-02. Justification and Scope of Proposed Modifications	3-2
a. Embankment Seismic Retrofit	
b. Hydrologic Adequacy	
c. Tainter Gate Reliability	
4. History of Maintenance and Rehabilitation	
4-01. General	4-1
4-02. Major Maintenance Activities	4-1
a. Embankment	
<u>Chapter and Sub-Chapter</u>	<u>Page</u>

b. Outlet Works	
c. Spillway	
5. Project Use	5-1
6. Consequence of No Dam Safety Modification	
6-01. General	6-1
6-02. Dam Vulnerable to Seismic Action	6-1
a. Degree of hazard	
b. Mode and magnitude of expected failure	
(1) Damage to the dam and related structures	
(2) Downstream impact	
6-03. Dam Hydrologically Deficient	6-3
a. Degree of hazard	
b. Mode and magnitude of expected failure	
(1) Damage to the dam and related structures	
(2) Downstream impact	
6-04. Effectiveness of Existing Flood Warning System and Evacuation Plans	6-3
a. General	
b. Flood warning system	
c. Evacuation plans	
7. Evaluation Process	
7-01. Nature of Dam Safety Problem	7-1
a. Hydrologic deficiency	
b. Seismic deficiency	
c. Other unsafe conditions; Tainter gates	
7-02. Extent of Deviation from Current Criteria	7-5
a. Hydrologic adequacy	
b. Seismic stability	
c. Other Features; Tainter gates	
7-03. Nature of Damages Associated with Dam Failure	7-7
a. Potential economic losses	
b. Description of population at risk	
c. Warning and evacuation	
d. Probable loss of life	
e. Economic losses with and without failure	

Chapter and Sub-Chapter	Page
f. Environmental and other critical losses	
7-04. Current Average Annual Benefits	7-16
a. General	
b. Historical flood control benefits	
c. Recreation	
d. Water supply contracts	
e. Loss of life; hydrologic deficiency with PMF event	
7-05. Alternatives Considered for Seismic Retrofit	7-18
a. General	
b. Brief Presentation of Alternatives	
A. No action	
B. Partial correction	
(1) Foundation seepage cutoff	
(a) Cutoff through the upstream slope	
(b) Cutoff through central core	
(2) Enhanced underseepage control system	
(a) Add reinforced relief wells	
(b) Add wells to be pumped	
(3) Enhanced emergency action planning	
(4) Restricted lake operation	
(5) Enhanced drainage capacity	
C. Complete Correction	
(1) Reinforce embankment	
(a) Reinforce structure with piles	
(b) Reinforce structure with anchors	
(2) Stabilize foundation soil	
(a) Removal and replacement of liquefiable material	
(b) Dynamic compaction (heavy tamping)	
(c) Vibroflotation	
(d) Jet grouting	
(e) Soil mixing	
(f) Stone columns	
(g) Gravel drains	
(3) Enlarge embankment	
(a) Berm upstream	
(b) Berm downstream	
(c) Buttress downstream	
D. Breach dam	
E. Replace embankment	
c. Results of initial screening	
d. Conclusions of the value engineering study	
(1) Rating criteria	

<u>Chapter and Sub-Chapter</u>	<u>Page</u>
<ul style="list-style-type: none"> <li>(2) Best rated alternatives <ul style="list-style-type: none"> <li>e. Cost evaluation</li> <li>f. Final evaluation</li> </ul> </li> </ul>	
7-06. Hydrologic Deficiency Remediation <ul style="list-style-type: none"> <li>a. Recommended remediation</li> <li>b. Cost evaluation</li> </ul>	7-34
7-07. Other Deficiencies Remediation	7-35
7-08. Summary of Costs.	7-40
8. Recommended Plan	
8-01. Selected Alternative and Rationale	8-1
8-02. Schedule of Funding Requirements	8-5
8-03. Cost Sharing	8-6
8-04. Local Cooperation	8-6
8-05. U.S. Fish and Wildlife Service Coordination Act Report	8-7
Attachment A: Inundation Maps (12 plates)	
Attachment B: Economic Damage and Loss of Life Reaches Maps (16 plates)	
<b>Appendices</b> (bound separately)	
<b><u>Appendices I, II, III, and IV</u> (VOLUME II of VII)</b>	
I. Community Involvement/Scoping	
II. Water Supply Contracts	
III. Hydrologic Adequacy Evaluation <ul style="list-style-type: none"> <li>Part 1 - Overtopping Failure</li> <li>Part 2 - Seismic failure</li> </ul>	
IV. Value Engineering Study	

**Appendices V and VI (VOLUME III of VII)**

V. Phase II Special Investigations. Part 1: Seismologic Investigation

VI. Phase II Special Investigations. Part 2: Detailed Field Investigation and Evaluation of Repair Alternatives.

**Appendices to Appendix VI (VOLUME IV of VII)**

- A. Expert recommendations
- B. Standard Penetration Tests
- C. Cone Penetrometer Tests
- D. Undisturbed Sampling and Laboratory Testing Summary

**Appendices to Appendix VI (VOLUME V of VII)**

- E. Slope Stability Analyses
- F. DYNAFLOW Seismic Deformation Analysis
- G. TARA Seismic deformation Analyses
- H. Seepage Analyses
- I. Cost Estimates
- J. Seismic Rehabilitation of the Dam

**Appendix VII (VOLUME VI of VII)**

VII. Phase II Special Investigations. Part 3: Outlet Works Evaluation

**Appendices VIII, IX, X, XI, and XII (VOLUME VII of VII)**

VIII. Cost Estimates for the Recommended Plan

IX. Project Management Plan

X. Real Estate

XI. Seismic Stability of Manhattan Levee

XII. Project Features and Paper on Tuttle Creek Dam Construction